

TOP SECRET

Copy 105
4 Pages

NPIC/R-384/63

December 1963

PHOTOGRAPHIC INTERPRETATION REPORT

MILITARY INSTALLATIONS,
GYOR, HUNGARY

DECLASS REVIEW by NIMA/DOD



CIA




DIA



25X1

NATIONAL PHOTOGRAPHIC INTERPRETATION CENTER



TOP SECRET

GROUP 1
Excluded from automatic
downgrading and declassification

MILITARY INSTALLATIONS, GYOR, HUNGARY

This report is a partial answer to DIA requirement DIAXX 63-84, to verify the location of selected military installations in Hungary and to perform a photo analysis to determine function, number and dimensions of buildings, to estimate troop capacity, to identify and describe related training areas and facilities, and to confirm or negate ammunition and POL storage.

25X1D

25X1

25X1D

25X1D

Photography of [redacted] was used for identification and mensuration of the installations and the buildings within them. The installations were observed on poor quality [redacted] photography of [redacted] [redacted] but no changes were apparent from the [redacted] photography.

The military installations described below and shown in Figures 1 and 2 have a total estimated troop capacity of 4,959.*

Gyor Army Barracks No 1 Rakoczi

Coordinates: 47-40-50N 017-38-22E

25X1D

Troop capacity: 2,541

This military installation located in south central Gyor covers eight acres and contains:

- 2 E-shaped probably three-story barracks buildings, each with a base 280 by 40, two wings 55 by 45, and one wing 85 by 30 feet
- 1 probably three-story barracks building 110 by 45 feet, a total for the three barracks buildings of 127,050 square feet
- 1 probably three-story administration building 80 by 55 feet, with a total of 13,200 square feet

*Troop capacity is computed on a basis of 50 square feet of space per man.

2 storage buildings, 220 by 40 and 100 by 40 feet, a total of 12,800 square feet
1 vehicle shed 320 by 30 feet
7 miscellaneous support buildings ranging from 180 by 40 to 30 by 20 feet
no observed ammunition or POL storage.

Gyor Army Barracks No 21

Coordinates: 47-40-05N 017-39-15E

25X1D

Troop capacity: 2,418

This installation located on the south-south-east edge of Gyor covers 23 acres and contains:

- 1 E-shaped probably two-story barracks building, with a base 140 by 30, two wings 30 by 15, and one wing 55 by 15 feet
- 1 T-shaped probably two-story barracks building, the base 110 by 40 and the wing 35 by 15 feet
- 12 probably two-story barracks buildings, four 100 by 25 and eight 90 by 55 feet, a total for the 14 barracks buildings of 120,900 square feet
- 1 one-story administration building 75 by 40 feet, with a total of 3,000 square feet
- 5 vehicle sheds, three 330 by 40 and two 300 by 40 feet
- 11 miscellaneous support buildings ranging from 250 by 40 to 40 by 15 feet
- 1 firing range 290 by 75 feet
no observed ammunition or POL storage.

Training Area and Ammunition Dump

Coordinates: 47-42-00N 017-42-00E (UTM
33TYN013870)

[redacted] (Gyor Training Area and

25X1D

25X1

Approved For Release 2002/08/26 : CIA-RDP78B04560A001000010026-9

Next 1 Page(s) In Document Exempt

Approved For Release 2002/08/26 : CIA-RDP78B04560A001000010026-9

NPIC/R-384/63

Ammunition Dump TA 1)

Troop capacity: not applicable

This training area and ammunition dump 3.2 miles north-northeast of Gyor covers approximately 2,000 acres.

The double-fenced ammunition dump is approximately 1,500 by 680 feet and includes:

5 revetted ammunition storage buildings, three 45 by 35 and two 20 by 10 feet, a total of 5,125 square feet

3 miscellaneous support buildings, one 40 by 20 and two 10 by 10 feet.

The training area facilities include:

1 tank firing range 2,250 by 520 feet

1 firing range 1,220 by 115 feet

5 miscellaneous support buildings ranging from 185 by 50 to 20 by 20 feet numerous trench systems and weapon emplacements scattered throughout the area.

This area does not appear to be well maintained.

Reported targets

The following previously reported installations were not observed:

POL storage facility at UTM 33TXN9884

POL storage facility at UTM 33TYN041872

REFERENCES

PHOTOGRAPHY



25X1D

MAPS OR CHARTS

ACIC. US Air Target Chart, Series 200, Sheet 0252-5HL, 3d ed, May 63, scale 1:200,000 (SECRET)
AMS. Series M773, Sheet 4959 E, 1st ed, 1951, scale 1:50,000 (UNCLASSIFIED)

REQUIREMENT

DIAXX 63-84

NPIC PROJECT

J-252/63 (partial answer)

Approved For Release 2002/08/26 : CIA-RDP78B04560A001000010026-9
~~TOP SECRET~~

~~TOP SECRET~~
Approved For Release 2002/08/26 : CIA-RDP78B04560A001000010026-9